

International Workshop on Dynamic Stability Challenges of the Future Power Grids

09/02/2025 - Baltic Power Systems Synchronisation with Continental Europe

Antons Kutjuns

AS Augstsprieguma tikls (AST)

Head of Development and Research Division





elering AST



Tuesday, September 9th 2025, Rome, Italy




- Introduction
- History
- Implementation of Synchronisation Project
- Conclusions






Till 08/02/2025. Synchronously and asynchronously







From 09/05/2025. Synchronously or asynchronously









2004-2025

01.05.2004 Baltic joined EU and

NATO



With possibility to use support from EU Funds

11.06.2007

Baltic Primer Ministers signed Communique

- On the transmission System Operators (TSO) of the three Baltic States to undertake a full feasibility study on the synchronization of the Baltic electricity transmission system with the UCTE synchronous area and to report back to the Prime Ministers by the end of the year on the cost and possible timetable of

2009-2023

Baltic and Polish TSOs synchro studies, where in 2018 concluded about inertia and frequency regulation requiremen



28.06.2018

Baltic States and Poland Primer ministers and EU president signed synchro political roadmap for synchro in the end of 2025



2019

27.05.2019. Connection Agreement with Catalogue of Measures for start of synchro in the end of 2025

20.06.2019 **Political** Roadmap



2021-2022

COVID-19 War in Ukraine

03/2022

Urgent synchronis ation Agreement 2023

Accelerated synchronisation

Baltic Primer

the Connection Agreement and

11/2023 approval

25/07/2023 -**Baltic MS** Agreement 01/08/2023 -Baltic TSOs CA

3/08/2023 -Ministers MoU

09/2023 -Amendments to CoM

Accelerated synchro roadmap

07/2024 Non renewal of

BRELL agreement

10/07/2024 - Ministries decision

16/07/2023 - Baltic TSOs signed

17/07/2024 - letters

sent out

letters

08/08/2024 delivery of the letters to RU/BLR

08/2024-02/2025

Preparation and work of CoM fulfilment

Baltic TSOs personnel training

26/11/2024 -**RGCE** decision

08/02/2025 desynchronis ation from **BRELL**

09/02/2025 synchronisati on with CE







Implementation of Synchronisation projects

Baltic Synchronisation project implementation was divided into two following Phases:

- ✓ Phase I internal transmission network infrastructure reinforcements in the Baltic States. This phase costs and benefits were evaluated by the first CBA completed in 2018 – Security of Supply. Co-financed by CEF.
- ✓ Phase II infrastructure investment items recommended by the dynamic and frequency studies prepared by Baltic and Polish TSOs. Costs and Benefits of Phase II are evaluated by the second CBA in 2019 SEW. Co-financed by CEF.
- ✓ Catalogue of Measure investments items, identified in the Catalogue of Measures, identified by ENTSO-E in 2019 under Connection Agreement, related for power system operation.

Invaluable political and financial support from EU and Member States:

- ✓ CEF co-financing, totally for EE, LV, LT un PL 1.7 billions EUR for all phases;
- ✓ RRF and RePowerEU financing 200 MEUR
- ✓ Modernisation Fund 100MEUR



















330kV transmission network reinforcement


	Totally planned	Status 08/02/2025	Status 12/2025
Estonia	3	3	-
Latvia	2	2	-
Lithuania	4	1	3

	Status 08/02/2025	Status 12/2030
Harmony link	-	1

BESS implementation

	Totally planned	Status 08/02/2025	Status 12/2025
Estonia	-	-	-
Latvia	WM08	-	80MW
Lithuania	200MW	200MW	-





Implementation of Synchronous Condensers

Scope:

9 synchronous condensers (SC) will be constructed in Estonia, Latvia and Lithuania to provide 17 100 MWs of additional grid inertia.

3 SC in each country will provide at least 5700 MWs of inertia.

	Totally planned	Status 08/02/2025	Status 12/2025
Estonia	3	3	-
Latvia	3	1	2
Lithuania	3	2	1


Status on 8/02/2025, totally in operation 6 SC from 9:

- Estonia: all 3 synchronous condensers (Kiisa, Pussi, Viru) were completed.
- Lithuania: 2 of 3 synchronous condensers (Alytus and Telšiai) were completed.
- Latvia: 1 of 3 synchronous condenser (Grobiņa) was completed.









Implementation of LFC

	Status 08/02/2025
Estonia	+
Latvia	+
Lithuania	+

Other critical IT and infrastructure projects

	Totally planned	Status 08/02/2025	Status 12/2025
Estonia	100%	70%	95%
Latvia	100%	70%	99%
Lithuania	100%	70%	95%









Baltic desynchronisation, isolated operation test and synchronisation process

Date	Time (EET) Time (CET)	Operation mode	Activity
2025.02.07 (Friday)	00:00-24:00 23:00-00:00		Preparation for the test
	06:00 – 07:25	Synchronous with IPS/UPS	Disconnection of Lithuania-Russia (Kaliningrad region) cross border lines
	07:25 – 09:00 6:25-08:00		Disconnection of Lithuania-Belarus, Latvia-Russia, Estonia-Russia cross border lines
2025.02.08	09:00 - 10:00		Normal Operation
(Saturday)	8:00 09:00 10:00-13:50	Isolated operation (Total 27 Hours)	(without additional disturbances) Performance frequency test (part 1)
	13:50-18:00		Performance frequency test (part 2)
	18:00-24:00		Normal Operation (without additional
	00:00-10:00		disturbances), preparation for synchronization with CESA
2025.02.09 (Sunday)	10:00-11:00		Performance of the voltage deviation tests (2 Part)
	11:00-13:00 10:00-12:00		Normal Operation preparation for synchronization with CESA
	13:00-14:00 12:00-13:00		Synchronization
	14:00		Synchronous operation with CESA "Trial operation"


Planned disconnection of 330kV overhead lines with third countries

Currently disconnected 330kV overhead lines with third countries









Baltic Systems desynchronisation 9:09 08/02/2025






Total **Demand** – 3285 MW Total **Generation** – 3281 MW Total **Inertia** – 30742 MW/sek







Baltic Systems Synchronisation. 14:05 09/02/2025



Time of synchronization: 2025 02 09 14:05:33







Baltic Systems Synchronisation official opening







Conclusions

- Historical event for the Baltic States
- Project for almost 20 years
- Project is politically and financially supported by EC and Baltic Member States
- > Project received several awards: ENTSO-E 2025-year project, PMI (USA) 2025 award in infrastructure nomination
- > The implementation of big infrastructure projects was very big challenge from finance and timeline prospectives
- > Despite COVID-19 pandemic and war in Ukraine, project implemented ~ 1 year before planned schedule
- > 70% of the projects have been implemented before 09/02/2025, rest of the projects till 2025 and some of the projects till 2030
- > The protection of synchronisation infrastructure, as critical infrastructure is one the next challenges in the Baltic States and Poland

 Control

 Control







Antons Kutjuns AST antons.kutjuns@ast.lv





